



GOVERNMENT OF BERMUDA
Ministry of Public Works

Department of Works and Engineering

PART 4

SPECIFICATIONS

For

REPAIRS TO FENCING IN ST. GEORGES PARISH

OCTOBER 2016



GOVERNMENT OF BERMUDA

Ministry of Public Works

Department of Works and Engineering

REPAIRS TO FENCING IN ST. GEORGES PARISH

TECHNICAL SPECIFICATIONS

- 01010-Summary of Work
- 01026-Unit Prices
- 01030-Alternates
- 01040-Project Co-ordination
- 01050-Field Engineering
- 01090-Definitions and Standards
- 01200-Project Meetings
- 01300-Submittals
- 01561-Environmental Protection
- 01631-Product Substitutions
- 01700-Contract Closeout

- 03000-Concrete General
- 03100-Concrete Formwork
- 03300-Cast-in-place Concrete
- 03370-Concrete Curing

- 06176-Metal-Plate-Connected Wood Trusses



GOVERNMENT OF BERMUDA

Ministry of Public Works

Department of Works and Engineering

SPECIFICATIONS

1. DESCRIPTION OF WORKS

- 1.1. The work included in this contract is for repairing and reconstruction of fencing in St. Georges along Barry Road from St. Catherine's Fort, along Grenadier Lane up until Gates Fort Park, inclusive Grenadier Lane fencing at Barry Road junction. See attached spreadsheet and pictures for fencing locations. There are two types of fencing: single railing and the double railing.

2. MATERIALS

- 2.1. **The Contractor shall be supplied with all fencing materials for constructing of the repairs.** Materials shall be fencing posts, fencing railing, galvanized bolts and concrete for footings. All pickup of materials will need to be scheduled with Wendall Eve, # 501-3062 and PO will be provided at acceptance of tender for the pickup of wood fencing from store.

3. EXECUTION

- 3.1. The Contractor shall review all fence repair locations with Government representative from Public Works and only repair those agreed upon in this contract listed on the attached spread sheet.
- 3.2. If additional fencing has been located or identified, the contractor shall seek approval from Government representative prior to undertaking repairs.
- 3.3. The repairs mainly consist of reinstalling detached lateral railings if post are in stable condition, reinstalling leaning posts, replacement of missing railings and missing posts.