



Addendum 1

**Questions & Answers**

- 1. Would the areas immediately located on each level adjacent to boiler #1 be appropriate laydown areas cladding?**

For plant operation, safety and plant housekeeping the areas around boiler #1 shall **NOT** be utilized as a laydown area. The main designated laydown area shall be on the six meter level (open area on bottom level of plant) shall be utilized as a laydown area.

- 2. Can you tell me who supplied the previous water walls for you when you did boiler 1?**

No we cannot provide information on the previous suppliers of the water walls.

**Clarifications**

1. Exposed tube material for the waterwalls shall be coated with Inconel material. All tubes that are covered by refractory do not require Inconel overlay.
2. J & G Refractories must be utilized for tile refractory replacement. See website information below & contact info:

[www.jg-refractories.com](http://www.jg-refractories.com)

Robert-Bosch-Straße 1  
68723 Schwetzingen  
Germany

Phone: +49 (0) 6202 - 944 - 0

Fax: +49 (0) 6202 - 944 - 194

email: [info@jg-refractories.com](mailto:info@jg-refractories.com)

3. Holding clips for tile refractory should have Inconel overlay as specified in the tender.



GOVERNMENT OF BERMUDA

Ministry of Public Works

---

**Department of Works and Engineering**